

DOCUMENT 00 91 13

ADDENDUM NO. 3

10-24-2016

PROJECT: WALTHAM POLICE STATION RENOVATION

CHANGES, CORRECTIONS AND CLARIFICATIONS

The attention of bidders submitting proposals for the above subject project is called to the following addendum to the specifications. The items set forth herein, whether of omission, addition, substitution or clarification are all to be included in and form a part of the proposal submitted.

THE NUMBER OF THIS ADDENDUM (NO. 3) MUST BE ACKNOWLEDGED IN DOCUMENT 004100 – FORM FOR GENERAL BID, PARAGRAPH B and in DOCUMENT 004113 – FORM FOR SUB BID. PARAGRAPH B

- This addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated **7-11-14** as noted below. (note the correction in the date to coincide with the issued documents 7-11-14)
- Please advise all sub-contractors.
- Acknowledge receipt of this Addendum in the space provided on the Bid Form.

GENERAL

Answers to Questions

1. Please verify if abrasive lines will be required to be installed on the Terrazzo treads in stairway #2 to meet current code as part of this renovation? **Yes, they are required**
2. Section 102210 - Wire Mesh Partitions: Please verify if the wire mesh cages with gates in the sallyport being provided new or 'salvaged' and re-installed used? **The Wire mesh partitions are new**
3. Section 105110 - Metal Lockers: Please verify if the metal lockers to be provided and installed by GC or by owner? If by GC, note the layout in the Men's and Women's cannot function as drawn. Drawer/bench units under lockers cannot meet at 90 degree corners and all lockers must have the built-in bench, not just those drawn east-west. Please advise. **Metal Lockers are provided and installed by the GC, all lockers shall have a built-in bench and drawers at all locations. The lockers on the outside walls shall be deleted all new lockers shall run east/west. Provide a total of 155 lockers for the Men and 30 for the women.**
4. We are bidding on the Tile 09300 for this project and need clarification on the following.
 - A. The Toilet Elevations show 4"x4" wall tile. The Spec and Finish Schedule calls for 6"x6" wall tile. Please confirm 6"x6" walls? **Use the 6"x6"**

- B. The Toilet floors show 2"x2" tile on Finish Plans A630, A631 and A632. The Specs and Finish Material Schedule call for 6"x6" tile floors. Please clarify if Floor tile is to be 6"x6" Natural Hues or 2"x2" Mosaic Unglazed Tile? **The floor tile shall be 2"x2" Mosaic unglazed tile.**
- C. Plumbing Plans call for "Pre-Fab Terrazzo Shower Receptors" at all Shower stalls. Are we to run Floor Tile into these Showers per A630 -A632 , Finish Plans or are they Pre-Fab" by Plumber? **Follow the finish plans and provide tile into the shower.**
- D. What is the Tile at the Backsplashes on A705? Is it 6"x6" Natural Hues? **Yes 6"x6" natural hues**

PROJECT MANUAL

SPECIFICATION SECTIONS

ITEM NO. 1 – Section 024100 – Demolition

- A. Para 1.2 B – Add the following item No. 8:
 - 8. Division 4 – MASONRY
 - a. Demolishing the masonry shown on the Drawings under Division 4 – MASONRY. Removal of such material shall be then done under this Section 024100 – DEMOLITION.

Item No. 2 - Section 040001- Masonry Work:

- A. Para 1.1 D – Add the following Reference Drawings to the list provided:
 - 52. SD101 BASEMENT DEMOLITION PLAN
 - 53. SD102 FIRST/SECOND FLOOR DEMOLITION PLAN
 - 54. S001 GENERAL NOTES
 - 55. S101 BASEMENT PLAN
 - 56. S102 FIRST FLOOR FRAMING PLAN
 - 57. S103 SECOND FLOOR FRAMING PLAN
 - 58. S301 SECTION AND DETAILS
 - 59. S303 SECTIONS AND DETAILS
 - 60. S304 SECTIONS AND DETAILS
 - 61. S402 ENLARGED FRAMING PLANS
 - 62. S501 TYPICAL DETAILS
 - 63. S502 TYPICAL DETAILS
 - 64. S506 TYPICAL DETAILS

Item No. 3 - Section 042000 – Unit Masonry

- A. Para 1.2 A – Add item No.7 –Demolition of Masonry shown on the Drawings.

Item No. 4 Section 050001 – Miscellaneous and Ornamental Iron

- A. Para 1.1 D – Add the following Reference Drawings to the lit provided:
 - 52. SD 102 FIRST/SECOND FLOOR DEMOLITION PLAN
 - 53. S001 GENERAL NOTES
 - 54. S102 FIRST FLOOR FRAMING PLAN

Waltham Police Station Renovation
Waltham, Massachusetts

55.	S301	SECTION AND DETAILS
56.	S304	SECTIONS AND DETAILS
57.	S501	TYPICAL DETAILS
58.	S504	TYPICAL DETAILS
59.	S506	TYPICAL DETAILS

Item No. 5 Section 055000

- A. Para 1.2 D – Delete the words “Not Applicable” and add “angles and anchors for casting into concrete.”

End of Addendum 3