

THE CITY OF WALTHAM
MASSACHUSETTS
PURCHASING DEPARTMENT
School St. & Lexington St. Sanitary Sewer & Water Main Improvements

ADDENDUM NO. 1

April 16, 2019

CHANGES, CORRECTIONS AND CLARIFICATIONS

The attention of bidders submitting proposals for the above subject project is called to the following addendum to the specifications. The items set forth herein, whether of omission, addition, substitution or clarification are all to be included in and form a part of the proposal submitted.

THE NUMBER OF THIS ADDENDUM (NO. 1) MUST BE ACKNOWLEDGED IN SECTION 00 30 00 Price Proposal.

ITEM 1: ANSWERS TO POSED QUESTIONS

Q1. Min thickness given as 6mm. Is that installed thickness or cured thickness?
A1. Cured thickness of CIPP liner shall be 6mm.

Q2. Work hours shown as 9am to 4pm per page SP-1. Can the work hours be extended?
A2. Per City Ordinance, no work shall be performed on Lexington Street between the hours of 7am- 9am and 4pm-6pm. The Contractor shall be limited per contract to work hours between 9am-4pm throughout the project area. As work progresses, the City will evaluate and MAY approve requests from the Contractor to work on School Street outside of the 9am-4pm timeframe on a case-by-case basis. The intent of the time restriction is to minimize traffic disruption in an already congested area. THE CITY WILL NOT GARUNTEE ANY ALLEVIATION FROM THE RESTRICTED WORK HOURS.

Q3. Bid quantities for CIPP do not match the lining work found on the plans. Can you please clarify all the lining work?
A3. All proposed CIPP lining is indicated on the Contract Drawings. CIPP lining work shall be compensated at the Unit Price per linear foot as indicated on the Bid Form and shall be measured by the actual quantity furnished, installed, and accepted in the field.

End of Addendum 1