

THE CITY OF WALTHAM
MASSACHUSETTS

PURCHASING DEPARTMENT

**ASBESTOS REMOVAL AND HYGIENE SERVICES
FOR CERTAIN AREAS OF THE FORMER BANKS SCHOOL**

ADDENDUM NO. 2

September 27, 2012

CHANGES, CORRECTIONS AND CLARIFICATIONS

The attention of bidders submitting proposals for the above subject project is called to the following addendum to the specifications. The items set forth herein, whether of omission, addition, substitution or clarification are all to be included in and form a part of the proposal submitted.

THE NUMBER OF THIS ADDENDUM (NO. 1) MUST BE ENTERED IN THE BLANK SPACE AT THE BOTTOM OF THE PRICE SHEET.

ITEM NO.: 1 DELETE ITEMS

1. Delete paragraph 6 of the Section 1.02- Summary of Work.
2. Delete the words: " ...and internal boiler components " in paragraph 8 of section 1.02 - Summary of Work.
3. Delete Price Sheet page (last page)

ITEM NO.: 2 REPLACE ITEM(s)

1. Replace the three-column Diagram in Section 1.02 c with the one attached here.

End of Addendum 2

**Price Sheet, Asbestos Abatement, Former Banks School Phase 2 and 3
Renovation**

		"a"	"b"
Location	Asbestos-Containing Material	Estimated Quantity	Add/Deduct Unit Price
First Floor	Pipe Insulation	1,795 LF	\$_____ per LF
	Pipe fitting insulation on fiberglass line	44 each	\$_____ per each
	12"x 12" tan floor tile and associated black mastic	1,500 sq ft	\$_____ per SF
	Pebble style sheet flooring and associated black mastic	300 sq ft	\$_____ per SF
	9"x 9" green floor tile	100 sq ft	\$_____ per SF
Second Floor	Pipe fitting insulation on fiberglass line	4 each	\$_____ per each
	12"x 12" tan floor tile and associated black mastic	100 sq ft	\$_____ per SF
	12"x 12" tan/brown streak floor tile	100 sq ft	\$_____ per SF
	9"x 9" green floor tile	100 sq ft	\$_____ per SF
	Pipe Insulation (assumed concealed inside walls)	100 sq ft	\$_____ per SF
	Total for Base Bid	\$ _____	

Please note that the price sheet above consists of two sections: the first is the base bid in column "a", the second is the unit pricing "b" which will be used as add/deduct in the event the estimated quantities are not accurate or additional work is needed.