

THE CITY OF WALTHAM
MASSACHUSETTS

PURCHASING DEPARTMENT

**ABATEMENT AND DEMOLITION OF THE
YOUNG BUILDING, 2018
509 Moody Street**

ADDENDUM NO. 3

Oct 30, 2018

CHANGES, CORRECTIONS AND CLARIFICATIONS

The attention of bidders submitting proposals for the above subject project is called to the following addendum to the specifications. The items set forth herein, whether of omission, addition, substitution or clarification are all to be included in and form a part of the proposal submitted.

This addendum must be acknowledged as received in your cover letter

ITEM 1: ANSWERS TO POSED QUESTION(S)

Q1. Is there an analytical report for the above referenced project?

A1. The caulk associated with the older first and second floor windows (~27 windows) and other asbestos-containing caulking materials should be assumed PCB-containing and removed/disposed as such. The store front windows were installed post 1978 so they do not need to be removed/disposed as PCBs.

End of Addendum 3