

THE CITY OF WALTHAM  
MASSACHUSETTS

PURCHASING DEPARTMENT

**Boiler Replacement, Waltham Library**

**ADDENDUM NO. 4**

Sept 13, 2017

**CHANGES, CORRECTIONS AND CLARIFICATIONS**

The attention of bidders submitting proposals for the above subject project is called to the following addendum to the specifications. The items set forth herein, whether of omission, addition, substitution or clarification are all to be included in and form a part of the proposal submitted.

THE NUMBER OF THIS ADDENDUM (NO.4) MUST BE ACKNOWLEDGED IN THE FORM FOR GENERAL BID SECTION 00310 A

---

**ITEM 1: ANSWERS TO POSED QUESTIONS**

**Q1.** In add alternate #1, the demolition plan calls to remove boilers 1,2 & 3. In addendum #3, it clarifies the add alternate #1 to provide one high efficiency boiler but it refers to "existing boiler to be removed". To what boiler does this refer to?

**A1.** The "existing boiler to be removed" is referring to the entire bank of existing boilers, B-1, B-2, B-3, all of which are to be demolished in Add Alternate #1

**Q2.** In addendum #3, question 2, the answer refers you to the drawing A3.04. What detail on that drawing pertains to the question of "what is the material thickness of the wall where venting penetrations are to be made"?

**A2.** Detail 14 on sheet A3.04. Sheet A3.09 details 28, 30, and 32 provide additional detail of penthouse wall construction. That sheet is attached. The wall construction in the area where the venting penetrations are to be made is ½" drywall on the interior, 2" foam core metal panel on the exterior of the building, and a 6" cavity containing insulation and steel studs. See attached drawing A3.09

**End of Addendum 4**

